Sl. No.	Particulars	Unit	No	L	B	D	Qty	Rate	Amount
1	2	3	4	5	6	7	8	9	10
3	Fabricating supplying and mounting MS cox of 16 SWG suitable for floor / wall mounting, fully weather proof with providion for better heat discription, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 sq cm and Rs. 0.33 (PRDE Ele. 2010-11, Page No.41, Item No.38b)	Sqm. Cm							
			20	120.00	60.00		144000.00		
			10	410.00	25.00		102500.00		
							246500.00	0.37	91205.00
4	Supplying and drawing 3 core flat PVC sheahted submersible pump cable manufactured with elecrolytic grade copepr with flexible copper conductor confirming to table 3 class 5 of IS : 8130-1984 and virgin grade PV insulation and sheathed suitable for working voltage up to 11.00 Volts. BWSSB SR 2012-13, Page No.408, Item No.30.(c)								
		Rmtr	1	2000.00			2000.00	159.50	319000.00
5	Supplying of L.T. UG Cable having aluminum conductor PVC insulated, sheathed, galvanized steel wire / steel tap armoured cable with PVC outer sheathing. 1.1. K.V. SR BWSSB 2011-12 Page No.426, Item No.10.(d)								
		Rmtr	1	200.00			200.00	236.50	47300.00
6	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete (as per civil PWD ELEC. SR 2010-11, .P.70, I.6(d)								
		Rmt	1	150.00			150.00	80.00	12000.00
7	Labour charge for laying of 1.1 KV class UG cable in existing trench GI pipe / stone ware pipe / on wall / on pole as required. PWD ELEC. SR 201-11, P.69, I. 5(a)								
		Rmt	1	200.00			200.00	8.00	1600.00
8	Supplying of 150mm dia pump set confirming to IS 8034:1989 AND i.s. 9283/1995 with latest amendements texmo, taroo equivalent brnazd with sepcified duty conditions and acesories 8034/2002 10HP /20 Stage								
	10 HP / 20 Stage	Nos.	3				3	37000.00	111000.00
	12.5 HP / 25 Stage	Nos.	1				1	43000.00	43000.00